ENGINEERING DEPARTMENT.

HASSAN DIVISION.

Dated 20th April 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 3 P.M., on 2nd May 1929, for constructing an Industrial School building at Hassan. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 750 (at 5% on Rs. 15,000) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing an Industrial School building at Hassan," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract for "Constructing an Industrial School" at Hassan.

Serial No.	Items of work	Per	Front Block	Rear wings or workshop	Compound wall	Clearing site
			Quantity	Quantity	Quantity	Quantity
1	Earthwork excavation for foundation ...	C.yds.	86	55	9	...
2	Burnt stone in clay for foundation ..	C.ft.	2,324	1,496	375	...
3	Burnt stone in mortar, basement ...	,,	1,449	629	...	...
4	Burnt brick in clay	,,	2,526	1,393	242	...
5	Burnt brick in mortar	,,	1,756	1,223	...	..
6	Burnt brick in chunam, archwork ...	,,	326	125	...	...
7	Burnt stone slabs 6" thick dressed and fixed.	S.ft.	573	278	33	...
8	Teakwood battened doors with frame, shutters and iron work, complete.	,,	322	...	..	...
9	Teakwood battened windows with frame, iron bars, shutters and with ventilators on top, complete.	,,	280	35	...	...
10	Teakwood windows with battened shutters outside and glazed shutters inside and ventilators on top.	,,	132	...	...	...
11	Teakwood ventilators with glazed or battened shutters.	,,	70	126	...	...
12	Rolled steel girders 8"×4"	Cwt.	21	...	...	...
13	Rolled steel joists $4\frac{3}{4}$"×$1\frac{3}{4}$"	,,	27	...	...	...
14	Honne wood work, wrought and put up with wood oiling.	C.ft.	94·66	197·67	...	...
15	Roofing with 1st Class Mangalore tiles on teak reepers.	Sqr.	14·30	29·70	...	..
15	Jack arched terrace 9" thick with plastering, complete.	,,	12·73	...	..	...
17	Ridge tiles set in mortar	R.ft.	72	118	...	...
18	Chunam mortar plastering	Sqr.	80·89	56·75	7·41	...
19	White and colour washing	,,	80·89	56·75	7·41	..
20	Cornice 9" thick with plastering, complete	R.ft.	377	...	12	...
21	Parapet wall 9" thick, $1\frac{1}{2}$ feet high, with base pillasters, coping, plastering, complete	,,	227	...	...	...

Serial No.	Items of work	Per	Front Block	Rear wings or workshop	Compound wall	Clearing site
			Quantity	Quantity	Quantity	Quantity
22	Ornamental teakwood, eaves board	R.ft.	72	291	...	...
23	Chocolate painting two coats	Sqr.	26·23	3·63	...	...
24	Tarring to wood work	L. S.	L. S.	L. S.	...	...
25	Flooring with Cuddapah slabs on 3" concrete with cement joints.	Sqr.	3·93	...	...	...
26	Flooring with 1st Class Mangalore tiles on 3" concrete with cement joints.	"	13·80	...	...	...
27	Pointing to basement	"	6·79	2·48	1·81	...
28	Chunam borders 6" thick	R.ft.	40	44	...	...
29	Masonry capitals and bases with cornice to pillars.	No.	16	...	...	...
30	Unforeseen items	L. S.	L. S.	L. S.	...	...
31	Teakwood finials and pendents	No.	...	12	...	...
32	Gravel flooring with cowdung wash	Sqr.	...	14·40	...	...
33	Masonry finials	No.	...	...	2	...
34	Burnt brick in chunam coping studded with glass pieces.	R.ft.	...	...	55	...
35	Wrought iron gate with painting	S.ft.	...	...	56	...
36	Lumpsum provision	L. S.	...	...	L. S.	...

N. KRISHNIENGAR,
Executive Engineer.

KOLAR DIVISION.

Notice dated 11th April 1929.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, dated 18th April 1929, Part VI, pages 316 and 317 calling for tenders for Restoring Thandramakalahalli Minor Tank, Chikballapur Taluk. Last date of tender is 8th May 1929.

N. LAKSHMINARASIMHAIYA,
Executive Enzineer.

MISCELLANEOUS DEPARTMENTS.

BANGALORE CENTRAL JAIL.

Notice dated 8th April 1929.

Notice is hereby given that sealed tenders will be received on Friday the 14th June 1929, by the Superintendent, Bangalore Central Jail for the supply by contract of articles required for petty construction and repairs in the Bangalore Central Jail during the year 1929-30.

Full details of supplies required and conditions for tenders are published in pages 318 and 319, Part VI of the *Mysore Gazette*, dated 18th April 1929.

K. SIDDHARAMAPPA,
Superintendent.

COPY OF THE PROCEEDINGS OF THE TRADING AND BANKING COMPANY, LTD., HIRIYUR, HELD ON 18TH MARCH 1929.

SUBJECT.

Mr. Ramanna proposed to wind up the Company and it was approved by the members of Committee, then present. Messrs A. M. Kallaiah and Siddanaik were appointed as liquidators.

H. Sidda Nayak,
Chairman.